

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-21010-00-00
Spot: SWNESE Sec/Twnshp/Rge: 14-10S-33W
2060 feet from S Section Line, 650 feet from E Section Line
Lease Name: SHEPHERD Well #: 1-14
County: THOMAS Total Vertical Depth: 4720 feet

Operator License No.: 35420
Op Name: ELK ENERGY HOLDINGS LLC
Address: 2250 N. ROCK RD. STE 118-107
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	344		240 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/05/2018 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 240 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 04/05/2018 12:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2800 w/50 sx
2nd plug @1825 w/100 sx
3rd plug @375 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

INVOICED

APR 10 2018

District: 04

Signed _____

Case Morris

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 09 2018

APR 16 2018

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS