

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20890-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 16-24S-4W  
990 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: LOWE Well #: 2  
County: RENO Total Vertical Depth: 3348 feet

Operator License No.: 5330  
Op Name: EXCALIBUR PRODUCTION COMPANY,  
Address: 1016 N MAIN PO BOX 278  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3341		
PROD	5.5	3348	634	75 SX
SURF	12.75	336		300 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/02/2017 12:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Revd. from: JASON FRIESE Company: \_\_\_\_\_ Phone: (620) 242-7918

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/09/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 3341' / SPOTTED 2 SX CEMENT ON PLUG. SET CIBP AT 3260' SPOTTED 2 SX CEMENT ON PLUG. SHOT 5 1/2" CASING OFF AT 634'. RAN IN WITH 2 7/8" TUBING TO 630'. SPOTTED 60 SX CEMENT. 150 LBS COTTONSEED HULLS. TAGGED CEMENT WITH SANDLINE AT 500'. RAN TUBING TO 384'. CIRCULATED TO SURFACE WITH 180 SX. 60/40 POZ 2% GEL. ON 8/9/17 PUMPED 23 SX CLASS A COMMON CEMENT, 25 FT DOWN 2" POLY TO FILL 12 3/4" CASING TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3319	3323		
3312	3313		

INVOICED  
MAY 01 2018

Remarks: COPELAND OUT OF BURRTON PROVIDED CEMENT FOR JOB

Plugged through:

District: 02

Signed B. J. HOPE

(TECHNICIAN)