

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24444-00-01
Spot: NWSESENW Sec/Twnshp/Rge: 4-32S-6E
3227 feet from S Section Line, 3281 feet from E Section Line
Lease Name: BELVEDERE Well #: 1
County: COWLEY Total Vertical Depth: 3600 feet

Operator License No.: 34950
Op Name: FUTURE ACQUISITION COMPANY LLC
Address: PO BOX 1129
FULSHEAR, TX 77441

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3587		275 SX
SURF	8.625	324		195 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2018 8:00 AM
Plug Co. License No.: 35553 Plug Co. Name: SOUTH CENTRAL WELL SERVICE LLC
Proposal Rcvd. from: AARON FROMAN Company: _____ Phone: (316) 993-7272

Proposed Plugging Method: AS KCC RULES & REGS/ CIBP @ 3150' W/2 SXS. CUT & PULL PIPE. CIRCULATE 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 3150' & DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1,000' & 530', LAYED DOWN 4 JOINTS CASING, WITH CASING @ 362', ELITE CEMENTING ESTABLISHED CIRCULATION. MIXED & PUMPED 120 SXS 60/40 POZMIX TO SURFACE. CEMENT CIRCUALTED. FINISHED LAYING DOWN 362' CASING, TAGGED WELL BACK TO SURFACE WITH 10 SXS. ELITE CEMENT TICKET #3786.

Perfs:

Top	Bot	Thru	Comments
3187	3294	CSG	


INVOICED
MAY 01 2018

Remarks: DENIED TA/ LACK OF LEASE

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

JK