

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-24013-00-00  
Spot: N2SESWSW Sec/Twnshp/Rge: 16-24S-14W  
450 feet from S Section Line, 990 feet from W Section Line  
Lease Name: CDK HOLDINGS Well #: 1  
County: STAFFORD Total Vertical Depth: 4337 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| SURF   | 8.625 | 410        |             | WITH 300 SX CMT |

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2018 2:00 PM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 4284' WITH 50 SX CMT. 2ND PLUG AT 950' WITH 50 SX CMT. 3RD PLUG AT 440' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE  
Date/Time Plugging Completed: 03/20/2018 4:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 4284' WITH 50 SX CMT. 2ND PLUG AT 950' WITH 50 SX CMT. 3RD PLUG AT 440' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: DP

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAR 28 2018  
KCC DODGE CITY

INVOICED  
MAY 01 2018