

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21858-00-01  
Spot: NESESWNW Sec/Twnshp/Rge: 16-14S-31W  
2004 feet from N Section Line, 1141 feet from W Section Line  
Lease Name: HESS Well #: 1-16  
County: GOVE Total Vertical Depth: 4750 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4725		175 SX
SURF	8.625	217		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/02/2018 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Revd. from: JOHN JOHNSON Company: GRAND MESA OPERATING COMP Phone: (620) 617-3357

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.  
CIBP set at 4528'.  
Perforations: 4518' - 4522', 4530' - 4538'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/02/2018 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 75 sx cement w/250 # hulls followed by 14 sx gel followed by 210 sx cement. Shut in pressure 700 psi. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 38.83941 -100.77657

Perfs:


Top	Bot	Thru	Comments
4530	4538		
4518	4522		

Remarks: QES CEMENT TICKET # 55066

Plugged through: CSG

District: 04

Signed



Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 02 2018

APR 16 2018

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
MAY 01 2018