

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-22022-00-00  
Spot: N2SWSENE Sec/Twnshp/Rge: 13-7S-18W  
2212 feet from N Section Line, 990 feet from E Section Line  
Lease Name: BALDERSTON Well #: 1  
County: ROOKS Total Vertical Depth: 3439 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3439		200 SX
SURF	8.625	1306		425 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2018 8:30 AM  
Plug Co. License No.: 33007 Plug Co. Name: RGN COMPANY, INC.  
Proposal Rcvd. from: ROLAND NYP Company: HERMAN L. LOEB, LLC DBA Phone: (785) 737-3242

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Production perforations: 3368' - 3384' Arbuckle

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2018 11:15 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 5 1/2" casing at 1250'. Ran tubing to 3357' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2300' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1326' and pumped 275 sx cement to circulate 5 1/2" casing and 8 5/8" x 5 1/2" annulus to surface with cement. Pulled all tubing. Topped off 5 1/2" casing with 25 sx cement.

GPS: 39.44510N -099.27142W

Perfs:

Top	Bot	Thru	Comments
3371	3374		
3368	3384		

INVOICED

MAY 01 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 733

Plugged through: TBG

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

APR 16 2018

Form CP-2/3

APR 02 2018

CONSERVATION DIVISION  
WICHITA, KS