

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40394-00-00
Spot: SENESE Sec/Twnshp/Rge: 3-25S-5E
2267 feet from S Section Line, 165 feet from E Section Line
Lease Name: CAMERON A Well #: 3
County: BUTLER Total Vertical Depth: 2501 feet

Operator License No.: 30582
Op Name: KISER, MICHAEL DBA MWK PETROLE
Address: 508 STONE LAKE CT
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2160		50 SX
SURF	10.75	44		39 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2018 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: MIKE KISER Company: _____ Phone: (316) 734-4810

Proposed Plugging Method: SAND TO 2425', DUMP BAIL 7 SXS ON TOP OF SAND, PULL CASING & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/05/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH WITH TUBING @ 2160', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 2% CC & DISPLACED IN CASING. TAGGED CEMENT @ 1860'. RIH ON WIRELINE PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES) RIH WITH TUBING @ 250', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. LAYED DOWN TUBING & TOPPED WELL BACK TO SURFACE WITH CEMENT.

Top	Bot	Thru	Comments
2477	2478	CSG	

INVOICED

Remarks: CEMENT TICKET #54855

MAY 02 2018

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

JK