

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20329-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 4-19S-37W
840 feet from N Section Line, 725 feet from W Section Line
Lease Name: KNOBBE Well #: 3-4
County: WICHITA Total Vertical Depth: 4855 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347		WITH 240 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/18/2018 11:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: HECTOR TORRES Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2390' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 03/19/2018 1:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

LOST CIRCULATION AT 4855'. PUMPED 300 SX CMT AT 3000'. GOT CIRCULATION BACK AFTER LETTING THE 300 SX CMT SET FOR 8 HOURS THEN PLUGGED. 1ST PLUG AT 2390' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 390' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QES.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
MAR 26 2018
KCC DODGE CITY

INVOICED
MAY 02 2018