

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-07268-00-00
Spot: NENESE Sec/Twnshp/Rge: 36-18S-11W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: DOLL Well #: 1
County: BARTON Total Vertical Depth: 3302 feet

Operator License No.: 30525
Op Name: LANGSTON OIL & GAS LLC
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3296		200 SX
SURF	8	292		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2018 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: D.S. LANGSTON Company: LANGSTON OIL & GAS LLC DBA Phone: (620) 786-0874

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Operator was set up to pull casing, had already sanded off perforations and topped with 5 sx cement at 2950'. Pulled stretch on casing. Parted at 500'. Dropped casing back onto parted casing and screwed back on to pipe. Will plug from 1500' below salt section.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/30/2018 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1300', 500' and 300'. Ran tubing to 1500' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 600' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 300' and pumped 70 sx cement. Circulated cement up casing.
03/30/2018 - Topped off with 30 sx cement.

GPS: 38.44102 -098.48176

INVOICED
MAY 02 2018

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

APR 11 2018

APR 16 2018

Form CP-2/3

APR 02 2018

CONSERVATION DIVISION
WICHITA, KS