

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-21332-00-00  
Spot: SWNWSESE Sec/Twnshp/Rge: 18-16S-10W  
752 feet from S Section Line, 1188 feet from E Section Line  
Lease Name: KOZISEK Well #: 5  
County: ELLSWORTH Total Vertical Depth: 3452 feet

Operator License No.: 33186  
Op Name: LB EXPLORATION, INC.  
Address: 2135 2ND RD  
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3245		
PROD	5.5	3444		100 SX
SURF	8.625	395		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2018 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Recvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method: TUBING FISH AT 2120'. RUN TUBING TO 2100' AND PUMP 100 SX'S COMMON WITH 3% CC. TAG CEMENT, THEN PERFORATE AT 1450, PUMP 35 SX'S COMMON 3% CC THRU TUBING & TAG. PERFORATE AT 1000', PUMP 35 SX'S COMMON 3% CC & LET SET 2 HOURS. PERFORATE AT 450' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/27/2018 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, ATTEMPTING TO PRODUCE WELL FROM KC ZONE - GOING BACK IN WITH TUBING. DROPPED 22 JTS-DID RECOVER 11 JOINTS, COULDN'T GET ANYMORE. RUN TUBING TO TOF AT 2100' AND PUMPED 150 SX'S COMMON WITH 3% CC ON 3-23-18. CAME BACK ON 3-26-18, COULDN'T TAG CEMENT. PUMPED 100 MORE SX'S COMMON WITH 3% CC. WAITED 2 HOURS, THEN TAGGED CEMENT AT 1898'. PERFORATED AT 1450', 1000', AND 450'. RUN TUBING TO 1450' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING OUT AND WAITED 1.5 HOURS AND TAGGED CEMENT AT 1300'. RAN TUBING BACK DOWN TO 1000' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING OUT. CAME BACK ON 3-27-18 AND TAGGED CEMENT AT 475' WITH TUBING. PULLED 1 JOINT AND PUMPED 30 SX'S CEMENT GETTING CIRCULATION TO SURFACE. SHUT VALVE AND PUMPED 40 MORE SX'S GETTING CIRCULATION FROM SURFACE CASING. PULLED TUBING OUT AND TOPPED OFF WITH 15 SX'S.

Perfs:

Top	Bot	Thru	Comments
3344	3452	OH	
3196	3202	CSG	
3082	3088	CSG	

Remarks: GRESSELL PERF TICKET #1695. COPELAND CEMENT #C-46122.

Plugged through: TBG

INVOICED

MAY 02 2018

District: 02

Signed Virgil Clothier  
(TECHNICIAN)