

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-063-21000-00-01
Spot: NWNWSENV Sec/Twnshp/Rge: 27-12S-30W
1647 feet from N Section Line, 3672 feet from E Section Line
Lease Name: LUBBERS OWWO Well #: 1-27
County: GOVE Total Vertical Depth: 4148 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4147		175 sx
SURF	8.625	330		200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2018 11:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GERALD WALKER Company: L. D. DRILLING, INC. DBA Phone: (620) 793-3051

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/450 # hulls.
DV Tool set at 2267' w/245 sx cement.
Perforations: 3889' - 3891', 3897' - 3899' and 4032' - 4035'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2018 7:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3826' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 3225' and pumped 50 sx cement w/200 # hulls. Pulled tubing to 2525' and pumped 75 sx cement. Pulled tubing to 1400' and pumped 100 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 25 sx cement. Backside full of cement. Shut in pressure 300 psi.

GPS: 38.98521 -100.64298

Perfs:

Top	Bot	Thru	Comments
4032	4035		
3897	3899		
3889	3891		

Remarks: SCHIPPERS CEMENT TICKET # 625

Plugged through: TBG

INVOICED

MAY 02 2018

District: 04

Signed _____

(TECHNICIAN)

CM

MAR 20 2018

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS