

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-60008-00-01
Spot: SENWSE Sec/Twnshp/Rge: 4-13S-14W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MACHIN OWWO Well #: 2
County: RUSSELL Total Vertical Depth: 3279 feet

Operator License No.: 5631
Op Name: LOEWEN OPERATOR, INC.
Address: 208 S MAIN PO BOX 335
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3279		150 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2018 8:30 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: JOHN DRISCOLL Company: LOEWEN OPERATOR, INC. DBA Phone: (785) 483-6446

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2018 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 200', 838' and 1250'. Ran tubing to 3000' and pumped 50 sx cement followed by 75 sx cement w/200 # hulls. Pulled tubing to 1270' and pumped 90 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 60 sx cement. Circulated cement out of the braden head. Shut in pressure 200 psi. Visually checked casing and cement was down 200' - 225' or 5 to 5 1/2 seconds down. Braden head was on a vacuum. Quality Cementing hooked to casing and pumped 70 sx cement w/50 # hulls. Circulated cement out of the braden head. Shut in. Hole standing full.

GPS: 38.94822 -098.87860

Remarks: QUALITY CEMENTING TICKET # 732

Plugged through: TBG

INVOICED
MAY 02 2018

District: 04

Signed Ray Dinkel
Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

APR 02 2018