

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-19053-00-00
Spot: NWNENESW Sec/Twnshp/Rge: 16-21S-11W
2431 feet from S Section Line, 2991 feet from E Section Line
Lease Name: SMITH ESTATE Well #: 5
County: STAFFORD Total Vertical Depth: 3470 feet

Operator License No.: 33288
Op Name: MANNING, GREGORY
Address: 574 SE 130 AVE
ELLINWOOD, KS 67526

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3372 | | WITH 2 SX CMT |
| PROD | 5.5 | 3465 | 0 | WITH 125 SX CMT |
| SURF | 8.625 | 275 | | WITH 200 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2018 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK ~~OR~~ SET CIBP @ 3372' WITH 2-5 SX CMT ON TOP. PERFORATE AT 600 & PUMP 10 SX GEL THEN CIRCULATE CMT TO SURFACE IN & OUT

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2018 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3372' WITH 2 SX CMT ON TOP. PERFORATE AT 600'. TIH WITH 2 3/8" TBG & BREAK CIRCULATION WITH FRESH WATER. CIRCULATES BOTH INSIDE & OUT OF 5 1/2" CASING. PUMP 255 SX CMT TO FILL HOLE TO SURFACE BOTH INSIDE & OUT. PULL & LAY DOWN TBG. TOP OFF HOLE WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3422 | 3427 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

INVOICED
MAY 02 2018

District: 01

Signed *Ken Scofield*
(TECHNICIAN)

RECEIVED
FEB 26 2018
KCC DODGE CITY

MP

5A