

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-22857-00-00
Spot: S2NESENW Sec/Twnshp/Rge: 26-8S-17W
3530 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HRABE Well #: 1-26 WSW
County: ROOKS Total Vertical Depth: 1994 feet

Operator License No.: 4472
Op Name: N.F. PRODUCERS, INC.
Address: 1236 N. FAVER DR
CASTLE ROCK, CO 80109

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1053		260 SX
SURF	8.625	127		80 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 02/21/2018 11:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: BRETT HILDEBRAND Company: N.F. PRODUCERS, INC. DBA Phone: (785) 871-7311

Proposed: Ordered 150 sx 60/40 pozmix 4% gel cement.
Plugging: 466' of 2 7/8" tubing pulled from well. Ran sandline with jars and stacked out at 517'.
Method: Perforations: 860' - 910'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2018 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 464' and pumped 60 sx cement to circulate cement to surface. Pulled all tubing. Hooked to 5 1/2" production casing and pumped 10 sx cement. Pressured to 200 psi. Hooked to 8 5/8" x 5 1/2" annulus and pressured immediately to 200 psi.

GPS: 39.33113N -099.18658W

Perfs:

Top	Bot	Thru	Comments
860	910		

Remarks: QUALITY OILWELL CEMENTING TICKET # 658

Plugged through: TBG

KCC WICHITA
MAR 16 2018

RECEIVED
INVOICED

MAR 09 2018

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

FEB 26 2018