

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21531-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 36-11S-33W
1491 feet from N Section Line, 1339 feet from E Section Line
Lease Name: ZERR Well #: 1
County: LOGAN Total Vertical Depth: 3800 feet

Operator License No.: 32016
Op Name: PIONEER RESOURCES INC.
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	224		225 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/11/2017 12:00 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 12/11/2017 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2650 w/50 sx
2nd plug @1590 w/100 sx
3rd plug @280 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:


Remarks: GLOBAL

Plugged through: DP

INVOICED

MAY 02 2018

District: 04

Signed 
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR 20 2018