

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21969-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 36-23S-5E
800 feet from S Section Line, 450 feet from W Section Line
Lease Name: JANZEN B Well #: 1
County: BUTLER Total Vertical Depth: 2614 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2605		100 SX
SURF	8.625	168		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2018 12:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL COMPANY Phone: (620) 222-4304

Proposed Plugging Method: As per State instructions

Plugging Proposal Received By: JONATHAN HILL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2018 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

	Top	Bot	Thru	Comments
1/31/2018: 1) Ran in w/ wireline and set CIBP at 2450', capped w/ 2 sks cement 2) Ran in w/ wireline and perforatted at 250' w/ 4 shots 3) Ran in w/ coiled tubing to 260', loaded hole w/ 10 bbls water. 4) Pumped 135 sks class A cement (60/40/4%) through coiled tubing, circulated up backside of 4.5" casing, then circulated to surface up 4.5" 5) Pulled out coiled tubing and topped off w/ cement. Plug falling, shut-in well	2501	2564		
2/5/2018: - Plug fell back >100' inside 4.5" and annulus				
2/8/2018: 1) Ran in w/ coiled tubing and tagged plug at 186' inside 4.5" 2) Pumped 65 sks 60/40/4% cement through tubing. Cement circulated up annulus to surface first, then up 4.5" casing to surface. Staying full.				

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICES. TICKET #: 45037

INVOICED

Plugged through: TBG

MAY 02 2018

District: 02

Signed J Hill
(TECHNICIAN)