

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23204-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 17-35S-7E
4757 feet from S Section Line, 609 feet from E Section Line
Lease Name: DOROTHY Well #: 9
County: COWLEY Total Vertical Depth: 3020 feet

Operator License No.: 4555
Op Name: ROADRUNNER ENERGY, INC.
Address: 6906 E 108TH ST
TULSA, OK 74133

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3020		375 SX
SURF	8.625	301		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2018 8:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JAMES GAFFNEY Company: _____ Phone: (918) 527-9247

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 03/16/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET @ 2000', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. PRESSURED CASING @ 300#, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 351' -352' (4 HOLES). ELITE CEMENTING SWEDGED INTO 5 1/2' CASING, ESTABLISHED CIRCUALTION, MIXED & PUMPED 120 SX 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. ELITE TICKET #3708.

Perfs:

Top	Bot	Thru	Comments
2042	2046	CSG	

INVOICED

Remarks: DENIED TA/ 10 YEAR

MAY 02 2018

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)