

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-017-20873-00-00  
Spot: NESWSEW Sec/Twnship/Rge: 28-18S-6E  
2245 feet from N Section Line, 1905 feet from W Section Line  
Lease Name: LIPS Well #: 1-28  
County: CHASE Total Vertical Depth: 1027 feet

Operator License No.: 5192  
Op Name: SHAWMAR OIL & GAS CO., INC.  
Address: 1116 E MAIN PO BOX 9  
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	992		120 SX
SURF	7	201		75 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/30/2017 12:00 AM  
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.  
Proposal Rcvd. from: BOB ROBINSON Company: SHAWMAR OIL & GAS Phone: (620) 382-7565

Proposed  
Plugging  
Method:

Run 1" to bottom, circulate cement to surface. Pull to 250'. Circulate to surface. Pull out 1". Top off hole.

Plugging Proposal Received By: JONATHAN HILL Witness Type: NONE  
Date/Time Plugging Completed: 05/30/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Run 1" pipe to bottom at 971'. Broke circulation to surface with fresh water. Mix 12 sacks cement and circulate to bottom. Pull 1" up 150'. Mix 10 sacks and circulate to surface. Pull 1" up 470'. Mix 10 sacks and circulate 5 sacks to surface. Pull 1" to 250' and circulate remaining 5 sacks to surface. Pull 1" out and top casing off with cement.

Perfs:

Top	Bot	Thru	Comments
485	493		
483	493		

INVOICED  
MAY 02 2018

Remarks: CEMENTING COMPLETED BY SHAWMAR OIL & GAS. PLUGGED DUE TO COMPLIANCE WITH 82-3-111 -- SHUT-IN OVER 10 YEARS

Plugged through: TBG

District: 02

Signed Jonathan Hill  
(TECHNICIAN)