

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20897-00-01
Spot: SWNWNE Sec/Twnshp/Rge: 21-32S-6E
4433 feet from S Section Line, 2434 feet from E Section Line
Lease Name: BOLACK B Well #: 2
County: COWLEY Total Vertical Depth: 3125 feet

Operator License No.: 31714
Op Name: NOVY OIL & GAS, INC.
Address: PO BOX 559
GODDARD, KS 67052

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3400		
PROD	4.5	3460		100 SX
SURF	8.625	225		225 SX
T1	2.375	3400		

Well Type: SWD UIC Docket No: D23465.0 Date/Time to Plug: 01/15/2018 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: KIRK GLENN Company: Phone: (620) 282-2212

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/22/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 3400', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES @ 275'-276' (4 HOLES). RIH WITH TUBING @ 375', COPELAND ACID MIXED & PUMPED 50 SXS CLASS A COMMON, NO CIRCULATION. WAITED 3 HOURS RIH WITH TUBING @ 375', COPELAND ACID MIXED & PUMPED 100 SXS CLASS A COMMON & DISPLACED TO 250'. SHUT WELL DOWN OVER NIGHT. TAGGED CEMENT @ 350', RIH WITH TUBING @ 290', COPELAND ACID MIXED & PUMPED 36 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3460	3800	OH	

INVOICED

Remarks: CEMENT TICKET #45020. FAILED MIT.

APR 27 2018

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1st