

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-20753-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 22-27S-16W
335 feet from S Section Line, 2366 feet from E Section Line
Lease Name: HARPER Well #: 4-22
County: KIOWA Total Vertical Depth: 4740 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4188		WITH 2 SX CMT
PROD	4.5	4738	1882	WITH 200 SX CMT
SURF	8.625	358		WITH 300 SX CMT

Well Type: SWD UIC Docket No: D27565.0 Date/Time to Plug: 03/01/2018 9:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Revd. from: RANDY GINEST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 4188' WITH 2 SX CMT. PLUG AT 1060' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: HEITH WALSH Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2018 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4188' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1070' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4238	4328		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED
APR 27 2018

District: 01

Signed Stephen J. Plaza
(TECHNICIAN)

RECEIVED
MAR - 7 2018
KCC DODGE CITY

Form CP-2/3

KMS