

3-28

2-060244

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-159-20,598.0000  
SW SE NW, SECTION 4 TOWNSHIP 20 RANGE 7W

OPERATOR LICENSE # 8061 2970 FEET FROM S SECTION LINE  
3630 FEET FROM E SECTION LINE

OPERATOR Oil Producers Inc. of Kansas  
NAME & Box 8647  
ADDRESS Wichita, KS 67208

LEASE NAME: Keller #1

COUNTY: Rice 119.27

WELL TOTAL DEPTH: 3670'

PIPE: 5-1/2" @ 3375'/150 sx

SURFACE CASING: 8-5/8" @ 257'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Rockhold Engineering, Inc.  
ADDRESS: Box 698, Great Bend, KS 67530 LICENSE: 5111

COMPANY TO PLUG AT: HOUR: am DAY: 28 MONTH: 3 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Jim Rockhold  
COMPANY NAME: Rockhold Engineering, Inc. PHONE: 316-792-2506

WERE: Sand to 3200' - cap w/5 sx cmt - shoot pipe - pull csq to 1075' - 35 sx cmt - pull csq to 675' - 35 sx cmt - pull csq to 307' - circ cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 2:00p DAY: 28 MONTH: 3 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Sanded to 3200' - capped w/5 sx cmt - shot pipe - pulled csq to 1075' - loaded hole w/water - 35 sx cmt - pulled csq to 675' - 35 sx cmt - pulled csq to 285' - circ 100 sx cmt to surface. PBTD 3345' - Perfs 3260 - 76' - recovered 2314' of 5-1/2"

REMARKS: B. J. Titan #635774 60/40 poz 2% gel

I DID OBSERVE THIS PLUGGING. PHIL WORLEY  
(BY THE COMMISSION)

Phil Worley  
R. Phil Worley (AGENT)

INVOICED  
DATE 4-11-91 APR 4 1991

INV. NO. 31492  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
REV. 3/90