

7-7

4-060412

E-23,996

API number: 15-009-23,801-A

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SE /4 SEC. 19 , 20 S, 12 W
1670 feet from S section line
2310 feet from E section line

Operator license #30349 Lease Batchman well #1-19

Operator: Vess-Transpacific Operating County Barton

Address: P.O. Box 781350 Well total depth 3700 feet
Wichita, Kansas 67278 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 250 feet

120.25

Aband. oil well ____, Gas well ____, Input well X, SWD ____, D & A ____

Plugging contractor: Co Tools License# -

Address: _____

Company to plug at: Hour: 9:30A.M. Day: 7 Month: July Year: 93

Plugging proposal received from: L.D. Davis Drilling, Inc.

Company: Consultant Phone: 316-793-3051

Were: Order 100 sxs. common and 300 sxs. 60/40 posmix - 10% gel. and
hulls. Perforate at lowest point above fish at 1303'. Junk tubing at
1303'. Plug through tubing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:30P.M., Day: 7, Month: July, Year: 93

Actual plugging report: 8 5/8" to 262'. 5 1/2" to 3630'. Perforate
at 1302' with 4 holes. Ran tubing to 1300'. Mix and pump 25 sxs.
common cement. Pull tubing to 1000' and pump 25 sxs. common cement.
Pull tubing to 700' and pump 50 sxs. common cement. Pull tubing to
270' and circulated cement up annulus and casing with 45 sxs. 60/40
posmix - 10% gel. Pulled tubing and shut in annulus. Tied onto
production casing and pumped 255 sxs. 60/40 posmix - 10% gel.
Max. 500#. S.I.P. 200#. Cement top next day at 30' from the surface.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD ____ Anhy. plug: YES X NO AUG - 2 1993

Bottom plug(in place): YES ____, CALC X, NO ____ Dakota plug: YES X, NO ____

Plugged through TUBING ____, CASING X. Elevation: GL

I did [] did not [] observe the plugging.

[Signature]
DHK (agent)

DATE 8-6-93
INV. NO. 38263