

5-18

To: 6 062155  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009.00363.0001

SE, SEC. 34, T 20S, R 14 W/Ex  
2130 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30040

Lease Name Pritchard Well # TR 3-2

Operator: Redstone Oil and Gas Co.  
Name & Address: Box 278  
Woodward, Ok. 73802

County Barton 115.44

Well Total Depth 3552 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 802

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 8:00 AM Day: 18 Month: May Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Mike Kelso - Kelso Casing Pulling Inc (phone) 316-938-2943

were: Order 200 sks 60/40 poz 8% gel 5 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00 PM Day: 18 Month: May Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8" set at 802' w/375 sks. 5 1/2" set at 3552' w/ 75 sks. Top perf at 3283'. Plugged bottom w/40 sks 60/40 poz 8% gel and set plug at 3000'. Shot pipe one time and recovered 1200'. Pumped in 8 5/8" .25 sks cement followed w/5 sks hulls in 175 sks cement w/1200 psi.

Remarks: By Allied. Ran line to 1000#.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-6-90

INV. NO. 28336

Signed Gilbert G. Scheck (TECHNICIAN) 5-31-90 E.g.g.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
MAY 31 1990