

4-071000

7-9

15.009.24521.0000

214

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-24,520

NW SE SE /4 SEC. 34, 20 S, 14 W  
990 feet from S section line  
990 feet from E section line

Operator license# 6627

Lease Marmie well # 1

Operator: Prospect Oil & Gas Co.

County Barton

Address: P.O. Box 837  
Russell, Kansas 67665

Well total depth 3600 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 803 feet

117.00

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allen Drilling License# 5418

Address: 1105 Walnut, P.O. Box 1389, Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 9 Month: July Year: 92

Plugging proposal received from: Mike Kern

Company: Allen Drilling Phone: 913-483-6266

Were: 8 5/8" - 803' S.P. cwc. w/375 sx. 60/40 pozmix - 2% gel. - 3c.c. by Allied Cement Company. Elv. 1900'. Anhy. 793'. No circulation problems. Mud condition 48 vis. - 9.9 wt. - 12 W.L. Proposal 155 sx. 60/40 pozmix - 6% gas. Spot with drill stem. Circulate hole. Heavy mud between all plugs. 25 sx. @ 3480' - 25 sx. @ 800' - 100 sx. @ 450' - 10 sx. @ 40' - 15 sx. in Rathole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 6:45P.M., Day: 9, Month: July, Year: 92

Actual plugging report: Allen Drilling ordered 155 sx. 60/40 pozmix and 6% gel. Circulated hole. Spotted and displaced cement through drill stem with heavy mud between all plugs.

1st. plug @ 3480' w/25 sx. cement.

2nd. plug @ 800' w/25 sx. cement.

3rd. plug @ 450' w/100 sx. cement.

4th. plug @ 40' w/10 sx. cement.

15 sx. in Rathole. (Circulate)

Remarks: Cemented by Allied Cement.

7-24-92

Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO

Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  NO

Plugged through TUBING  , CASING  . Elevation: 1900 GL

I did  / did not  observe the plugging.

DATE AUG 07 1992

INV. NO. 35886

7-9 OCT 28 1992

RECEIVED  
CONSERVATION COMMISSION  
AUG 24 1992  
(agent) Marion J. Schmidt  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-273

INVOICED