

4-020056

7-24

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-009-21,336.0000  
NE SW NW /4 SEC. 34, 20 S, 14 W  
3630 feet from S section line  
4290 feet from E section line

Operator license# 5030  
Operator: Vess Oil Corporation  
Address: 8100 E. 22nd Street  
North Building #300  
Wichita, Kansas 67226

Lease: Woodburn Well # 4  
County: Barton 119.80  
Well total depth 3686 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 824 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 8:30 A.M. Day: 24 Month: July Year: 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing & Salvage, Inc. Phone: 316-636-2525

Were: Shot off 5 1/2" at 1796'. Perfs at arbuckle 3567' - 3569'. LKC 3412' - 3417' -  
3429' - 3433' and 3447' - 3450' cast iron bridge plug at 3520'.  
Ordered 205 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received by: Case Morris  
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:45 A.M., Day: 24, Month: July, Year: 1998

Actual plugging report: 8 5/8" set at 824' w/400 sxs cement. 5 1/2" set at 3620' w/200 sxs cement. Sanded to 3360' and topped with 5 sxs cement with dump bailer. Shot casing off at 1796'. Pulled casing to 1550' - tied onto 5 1/2" - pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled casing to 850'. Tied on 5 1/2" - pumped 40 sxs cement with 100# hulls. Pulled casing to 250'. Tied on 5 1/2" - pumped 50 sxs cement. Circulated cement. POOH casing. Topped off hole with 15 sxs cement.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1904 GL

I did  did not  observe the plugging.

Jay Pfeiffer (agent)

Form CP-2/3

INVOICED  
DATE JUL 31 1998  
51022

RECEIVED  
KANSAS CORP  
1998 JUL 29 10

7-29-98

THO