

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24761-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 35-20S-14W  
4440 feet from S Section Line, 3530 feet from E Section Line  
Lease/Unit Name: WRIGHT B Well Number: 1  
County: BARTON Total Vertical Depth: 2684 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Production Casing Size: 0 feet: 0  
Surface Casing Size: 8.625 feet: 329 87.23  
225 SX CMT

Well Type: DH UIC Docket No: Date/Time to Plug: 08/02/2003 11:00 PM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Revd. from: GARY TALBOTT/GARY PU Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: Ordered 130 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 08/02/2003 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

1st. Plug at 820' w/25 sxs cement.  
2nd. Plug at 430' w/80 sxs cement.  
3rd. Plug at 40' w/10 sxs cement.  
Rathole with 15 sxs.  
Anhydrite 814' - 835'.  
Total of 130 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

RECEIVED  
AUG 13 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #15984.

Plugged through: DP

District: 04

Signed

Roger L Moses  
(TECHNICIAN)

INVOICED

DATE 8-13-03

INV. NO. 2004060398

Form CP-2/3

AUG 11 2003