

4-29

2-070690

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-20,425-0000

NE NE NE, SECTION 31 TOWNSHIP 20 RANGE 9W

OPERATOR LICENSE # 7546 4950 FEET FROM S SECTION LINE
OPERATOR MALONE OIL COMPANY 330 FEET FROM E SECTION LINE
NAME & 1591 RUGBY CIRCLE
ADDRESS THOUSAND OAKS, CA 91360

LEASE NAME: CAYWOOD #1
COUNTY: RICE
WELL TOTAL DEPTH: 3340' 108.55'
PIPE: 5 1/2" @ 3337'
SURFACE CASING: 8 5/8" @ 200'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: P.O. BOX 467, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 1:00 DAY: 29 MONTH: 4 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DARRELL

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3200' AND 5 SACKS

35 SACKS AT 1150'

35 SACKS AT 750'

250 TO 0'

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 1997

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { X }

COMPLETED: HOUR: 5:00 DAY: 29 MONTH: 4 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3200' AND 5 SACKS. SHOT 5 1/2" CASING OFF AT 2420'.
PULLED TO 1150', PUMPED 35 SACKS. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 250', PUMPED
CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

I DID NOT OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

INVOICED
DATE MAY 07 1997
48082