

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-03158-00-00
Spot: NESENW Sec/Twnshp/Rge: 29-15S-12W
1650 feet from N Section Line, 2970 feet from E Section Line
Lease Name: STEINLE B Well #: 3
County: RUSSELL Total Vertical Depth: 3321 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3310		75 SX
SURF	8.625	300		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2018 8:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: BANDY, TERRY P. DBA TE-PE OIL Phone: (620) 628-4428

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 10 sx gel and 200 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2018 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 815' and 1250'. Ran tubing to 2850' and pumped 10 sx gel followed by 50 sx cement. Pulled tubing to 1300' and pumped 75 sx cement. Pulled tubing to 600' and pumped 40 sx cement. Circulated cement to the pit. POOH. Hooked to braden head and pumped 5 sx cement. Pressured up to 400 psi. Filled casing with 15 sx cement. Hole standing full.

GPS: 38.72123 -098.68118

Perfs:

Top	Bot	Thru	Comments
3310	3321		
3058	3227		

INVOICED
MAR 01 2018

Remarks: QUALITY CEMENTING TICKET # 766

Plugged through: TBG

District: 04

Signed Ray Dinkel
Received _____ (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR 26 2018