

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21444-00-00
Spot: SENENENW Sec/Twnshp/Rge: 21-12S-32W
380 feet from N Section Line, 2380 feet from W Section Line
Lease Name: YOUNKIN RDC Well #: 1
County: LOGAN Total Vertical Depth: 4675 feet

Operator License No.: 34917
Op Name: BICKLE ENERGIES LLC
Address: PO BOX 816
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4674		570 SX
SURF	8.625	259		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2018 8:00 AM
Plug Co. License No.: 35469 Plug Co. Name: FRANKS OILFIELD SERVICE, LLC
Proposal Rcvd. from: MATT BICKLE Company: BICKLE ENERGIES LLC DBA Phone: (785) 639-1681

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 1400 # gel and 500 # hulls.
8 5/8' surface casing set at 259' w/170 sx cement.
5 1/2' production casing set at 4674' w/150 sx cement.
Multistage collar set at 2542' w/420 sx cement.
TD 4675'. PBTD 4648'.
Perforations: 4097' - 4100', 4214' - 4217' and 4556' - 4561'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2018 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4076' and pumped 1400 # gel followed by 100 sx cement w/500 # hulls. Pulled tubing to 2525' and pumped 125 sx cement. Pulled tubing to 1275' and pumped 125 sx cement. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and immediately pressured to 300 psi.

GPS: 39.00237N -100.87987W

Perfs:

KCC WICHITA
MAR 16 2018
RECEIVED
INVOICED
MAY 01 2018

Remarks: FRANKS OILFIELD SERVICE LLC PULLING UNIT. QUALITY OILWELL CEMENTING TICKET # 709

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

FEB 26 2018