

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-19126-00-00
Spot: NWSENW Sec/Twnshp/Rge: 35-11S-18W
1650 feet from N Section Line, 1650 feet from W Section Line
Lease Name: GSL WEST A Well #: 2
County: ELLIS Total Vertical Depth: 3706 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3704		150 SX
SURF	10.75	250		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2018 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILL BOWMAN Company: BOWMAN, WILLIAM F. DBA THE Phone: (785) 259-1297

Proposed Plugging Method: 02/26/2018 - Ordered 500 sx 60/40 pozmix 4% gel cement, 18 sx gel and 600 # hulls.
02/27/2018 - Ordered 275 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
Deep casing leaks.
Perforations: 3150' - 3154', 3314' - 3318', 3316' - 3321', 3448' - 3476' and 3599' - 3604'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2018 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1850', 1416', 885' and 225'. Bowman ran in hole with tubing to 3140'. Quality rigged to tubing, mixed and pumped 18 sx gel followed by 100 sx cement w/300 # hulls mixed in. Pulled tubing to 1811'. Quality rigged to tubing and pumped 145 sx cement w/300 # hulls mixed in. Pulled tubing to 925' and pumped 255 sx cement with no circulation. Left set overnight.
02/27/2018 - Ran in hole to 700' and tagged cement. Pumped 150 sx cement w/1000# hulls mixed in to circulate cement up 7" casing. Pulled tubing and topped off 7" casing with 15 sx cement. Hole standing full. Rigged to 10 3/4" surface casing and pumped 10 sx cement to pressure. Cement came out of backside of head.

GPS: 39.05491 -099.29070

Perfs:

Top	Bot	Thru	Comments
3599	3604		
3448	3476		
3316	3321		
3314	3318		
3150	3154		

KCC WICHITA
MAR 16 2018
RECEIVED

Remarks: QUALITY OILFIELD CEMENTING CO. TICKET # 711 AND 712

INVOICED

Plugged through: TBG

MAY 01 2018

District: 04

Signed _____

(TECHNICIAN)

CM