

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-22649-00-00  
Spot: SENWNWNW Sec/Twnshp/Rge: 34-16S-25W  
4931 feet from S Section Line, 4921 feet from E Section Line  
Lease Name: WEBSTER Well #: 1  
County: NESS Total Vertical Depth: 4460 feet

Operator License No.: 30104  
Op Name: CAMBRON, PAUL L.  
Address: 118 N PENN PO BOX 384  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4451	0	WITH 800 SX CMT
SURF	8.625	264		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2018 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5051

Proposed Plugging Method: PUMP 80 SX CMT & 200# HULLS ON BOTTOM. CIRCULATE CMT TO SURFACE FROM 1900'. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: \_\_\_\_\_ KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

RAN TBG TO 4330' & SPOTTED 80 SX CMT & 150# HULLS. PULLED TBG TO 1900' & PUMPED 110 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. TIED ONTO BACKSIDE & PUMPED 55 SX CMT. PRESSURED TO 300# & HELD.

Top	Bot	Thru	Comments
4451	4466	CSG	


INVOICED  
MAY 01 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY CEMENTING.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
MAR - 6 2018  
KCC DODGE CITY



Form CP-2/3

KMS