

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23813-00-00
Spot: N2N2NW Sec/Twvshp/Rge: 8-21S-11W
4950 feet from S Section Line, 3960 feet from E Section Line
Lease Name: HAYES Well #: C-1
County: STAFFORD Total Vertical Depth: 3488 feet

Operator License No.: 6768
Op Name: CARRIE EXPLORATION & DEVELOPM
Address: 1611 COPPER CREEK CT.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3390		
PROD	5.5	3507	2032	WITH 125 SX CMT
SURF	8.625	262		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2018 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP ABOVE ARBUCKLE. SAND BACK TO 3140' WITH 5 SX CMT. PLUG AT 610' WITH 12 SX GEL & 50 SX CMT. PLUG AT 310' WITH 50 SX CMT. PLUG AT 310' WITH 20 SX CMT.

Plugging Proposal Received By: KEN SCOFIELD Witness Type: NONE
Date/Time Plugging Completed: 02/27/2018 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3390'. SANDED BACK TO 3135' WITH 5 SX CMT. 1ST PLUG AT 610' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3415	3442		
3356	3358		
3294	3296		
3219	3221		
3188	3190		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENT.

INVOICED
MAY 01 2018

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
MAR - 9 2018
KCC DODGE CITY