

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23838-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 32-22S-14W
2982 feet from S Section Line, 2302 feet from E Section Line
Lease Name: CONCEPT Well #: 1
County: STAFFORD Total Vertical Depth: 4095 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4090	2068	WITH 175 SX CMT
SURF	8.625	462		WITH 400 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2018 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY Phone: (620) 793-9090

Proposed Plugging Method: SAND BACK TO 50' ABOVE TOP PERFS & TOP WITH 4 SX CMT. CUT & PULL CASING. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 490' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2018 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK TO 3800' WITH 5 SX CMT PLACED ON TOP. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3989	4003		
3905	3975		

INVOICED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

MAY 01 2018

Plugged through: CSG

District: 01

Signed

Ken Scofield
JA

(TECHNICIAN)

RECEIVED
MAR 20 2018
KCC DODGE CITY