

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-19311-00-01
Spot: NESESW Sec/Twnshp/Rge: 1-13S-16W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WIELAND UNIT Well #: 7-3
County: ELLIS Total Vertical Depth: 3318 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3312		150 SX
SURF	8.625	988		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2018 8:30 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Revd. from: NEIL PFANNESTIEL Company: CITATION OIL & GAS CORP. DBA Phone: (785) 798-2300

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement w/700 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2018 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 1600' and 885'. Ran tubing to 3000' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 2000' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 80 sx cement. Circulated cement to the pit. POOH. Hooked to casing and pumped 180 sx cement w/100 # hulls. Circulated cement out of the braden head. Shut in braden head. Pressured casing to 400 psi and shut in casing.

GPS: 38.94642 -099.04979

INVOICED
MAY 01 2018

Remarks: BASIC ENERGY SERVICES TICKET # 16158

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 26 2018

APR 16 2018

CONSERVATION DIVISION
WICHITA, KS