

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26195-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 3-19S-12W
2232 feet from S Section Line, 1877 feet from W Section Line
Lease Name: BILLY GENE "A" Well #: 1-3
County: BARTON Total Vertical Depth: 3415 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC
Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3418	2235	150 SX
SURF	8.625	320		230 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/22/2018 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: NICHOLAS HESS Company: COBALT ENERGY LLC Phone: (316) 201-4101

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2018 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Set CIBP at 3250'. Cut casing at 2235'. Pulled casing to 1435' and pumped 125 sx cement w/300 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 650' and pumped 40 sx cement. Pulled casing to 300'. Circulated cement to surface with 80 sx cement. Pulled casing and topped off with 40 sx cement.

GPS: 38.42625 -098.63934

Perfs:

Top	Bot	Thru	Comments
3303	3309		
3270	3272		
3257	3264		
3246	3249		

Remarks: BASIC SERVICES

Plugged through: CSG

District: 04

Signed

Bruce Rodie

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 16 2018

Form CP-2/3

MAR 26 2018

CONSERVATION DIVISION
WICHITA, KS

INVOICED
MAY 01 2018