

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-19136-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 32-13S-15W
4030 feet from S Section Line, 3465 feet from E Section Line
Lease Name: MERMIS D Well #: O-43
County: RUSSELL Total Vertical Depth: 3319 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO 205
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5"	3319		250 SX
SURF	8.625	243		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2018 8:30 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: JEFF CRAWFORD Company: CRAWFORD, JEFF DBA LONESTAR Phone: (785) 735-4585

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2018 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 975'. Hole in casing at approximately 1650'. Had a hole at 406'. Squeezed with 250 sx class A 3% c.c. Drilled out 200'. Ran tubing to 2850' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1850' and pumped 125 sx cement w/250 # hulls. Pulled tubing to 625' and pumped 70 sx cement. Circulated cement to pit. POOH. Hooked to braden head and pumped 0 sx cement at 150 psi. Topped off casing with 40 sx cement.

GPS: 38.88154 -099.01445

KCC WICHITA
MAR 16 2018
RECEIVED
INVOICED
MAY 01 2018

Remarks: GLOBAL CEMENTING TICKET # 3258

Plugged through: TBG

District: 04

Signed Ray A Dinkel

(TECHNICIAN)

CM

FEB 20 2018