

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-04223-00-00  
Spot: NENENE Sec/Twnshp/Rge: 21-18S-11W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MAES Well #: 1  
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 4871  
Op Name: CURT'S OIL OPERATION, LLC  
Address: PO BOX 8  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3336		125 SX
SURF	8.625	247		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2018 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITCHMANN Company: CURT'S OIL OPERATION, LLC DB Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/06/2018 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1350', 600' and 200'. Ran tubing to 2911' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2000' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1000' and pumped 70 sx cement. Pulled tubing to 250'. Circulated cement to surface on casing with 55 sx cement. Closed in casing. Circulated cement to surface on surface pipe with 5 sx cement. Pulled tubing. Topped off with 5 sx cement.

GPS: 38.47754 -098.53709

Perfs:

Top	Bot	Thru	Comments
3214	3224		
3103	3127		
3055	3065		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

INVOICED  
MAY 01 2018

District: 04

Signed Bruce Rodie

Received  
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

CM

APR 09 2018

APR 16 2018

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS