

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-039-20041-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 9-4S-27W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: PETRACEK LEASE Well #: 4  
County: DECATUR Total Vertical Depth: 3750 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 4.5 3739 100 SX

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

SURF 7 232 135 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/15/2018 8:00 AM

Plug Co. License No.: 33755

Plug Co. Name: QUALITY PLUS OILFIELD SERVICES, LLC

Proposal Rcvd. from: RODNEY REYNOLDS

Company: BEREXCO LLC DBA

Phone: (316) 265-3311

Proposed  
Plugging  
Method:

Ordered 400 sx 60/40 pozmix 4% gel cement w/750 # hulls.  
7" surface casing set at 232' w/135 sx cement.  
4 1/2" production casing set at 3759' w/100 sx cement.  
TD 3750'.  
Perforations: 3542' - 3546', 3557' - 3562', 3583' - 3587', 3594' - 3596', 3639' - 3643', 3668' - 3672' and 3707' - 3710'.  
Casing squeezes: 1887' w/130 sx cement and 2555' w/150 sx cement.  
Lockset packer stuck in 4 1/2" casing at 3460'. Fill-up above packer. Toronto and Lansing perforation below packer.  
Emporia and Burlingame perforation open above packer.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/15/2018 12:50 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Ran tubing to 3420' and pumped 80 sx cement (20 sx with out hulls and 60 sx with 250 # hulls).  
Pulled tubing to 2447' and pumped 80 sx cement w/250 # hulls. Pulled tubing to 1225' and  
pumped 80 sx cement w/200 # hulls. Circulated with cement. Pulled tubing to surface.  
Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 7" surface  
casing and pumped 30 sx cement. Shut in pressure 100 psi.

GPS: 39.72401N -100.35687W

3-16-18  
KCC WICHITA  
MAR 16 2018  
RECEIVED

Remarks: QES PUMPING SERVICES TICKET # 55,022. QUALITY PLUS OILFIELD SERVICES PULLING UNIT.

Plugged through: TBG

INVOICED  
APR 20 2018

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

CM

FEB 16 2018