

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-02678-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 25-20S-9W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: TOBIAS LEASE Well #: 12  
County: RICE Total Vertical Depth: 3363 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3291		
PKR	5.5	3294		
PROD	5.5	3358		100 SX
SURF	8.625	203		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/05/2018 11:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO LLC Phone: (316) 772-6449

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/06/2018 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1150', 750', AND 255'. RUN TUBING TO 3270' AND PUMP 50 SX'S COMMON CEMENT WITH 100#S COTTON HULLS. PULL TUBING TO 2850' AND PUMP 60-40 POZ, 4% GEL UP TO 1150', THEN PUMP 35 SX'S COMMON CEMENT. PULL TUBING OUT AND COME BACK NEXT DAY AND TAGGED CEMENT AT 1000'. RUN TUBING TO 950' AND PUMPED 50 SX'S COMMON, PULLED TUBING TO 550' AND CIRCUALTED CEMENT TO SURFACE. SHUT VALVE ON CASING AND CIRCUALTED CEMENT OUT OF SURFACE CASING WITH 460#S PRESSURE. PULLED TUBING OUT AND TOPPED OFF. USED 455 SX'S TOTAL.

Perfs:

Top	Bot	Thru	Comments
3274	3278	CSG	

Remarks: PERF TECH TICKET #14057. GLOBAL CEMENT TICKET #S 3274 & 3275

Plugged through: TBG

INVOICED

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

APR 09 2018