

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-21232-00-00  
Spot: NWSWNESE Sec/Twnshp/Rge: 29-14S-32W  
1860 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: KREBS P Well #: 1  
County: LOGAN Total Vertical Depth: 4380 feet

Operator License No.: 34639  
Op Name: BLACK TEA OIL, LLC  
Address: 11310 E. 21ST N. PMB #139  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4380		230 SX
SURF	8.625	261		180 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2018 9:00 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: CHRIS LEIKER Company: BLACK TEA OIL, LLC DBA Phone: (316) 744-5482

Proposed Plugging Method: Ordered 150 sx common cement 3% cc, 350 sx 60/40 pozmix 4% gel cement, 1600 # gel and 500 # hulls.  
8 5/8" surface casing set at 261' w/180 sx cement.  
5 1/2" production casing set at 4380' w/230 sx cement.  
Port collar set at 2070' w/430 sx cement.  
TD 4380'. PBTB 4354'.  
Perforations: 3638' - 3642', 3669' - 3674', 3997' - 4004', 4084' - 4088', 4140' - 4146', 4220' - 4264' and 4294' - 4304'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/28/2018 3:50 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 3614' and pumped 150 sx common cement 3% cc mixed with 400 # hulls. Pulled tubing to 2500' and flushed tubing with fresh water. Waited on cement for 1 1/2 hours. Ran polish rod on sand-line through tubing to tag cement at 3027'. Ran tubing to 3000' and pumped 1100 # gel. Pulled tubing to 2085' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 1100' and pumped 115 sx cement w/50 # hulls. Cement circulated to surface. Pulled tubing to surface. Topped off 5 1/2" casing with 10 sx cement. Casing full of cement. Connected to 8 5/8" surface casing and pumped 15 sx cement. Maximum pressure 300 psi.

GPS: 38.80546N -100.89603W

Perfs:

Top	Bot	Thru	Comments
4294	4304		
4220	4264		
4140	4146		
4084	4088		
3997	4004		
3669	3674		
3638	3642		

3-16-18  
KCC WICHITA  
MAR 16 2018  
RECEIVED

Remarks: ULTIMATE WELL SERVICE LLC PULLING UNIT. COPELAND ACID AND CEMENT TICKET # 46 ~~NOTICED~~

Plugged through: TBG

APR 20 2018

District: 04

Signed: Darrel Dipman

(TECHNICIAN)

CM

MAR 01 2018