

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21380-00-00
Spot: SENWSENW Sec/Twnshp/Rge: 29-14S-32W
1950 feet from N Section Line, 1895 feet from W Section Line
Lease Name: ROSE TRUST B Well #: 3
County: LOGAN Total Vertical Depth: 4331 feet

Operator License No.: 34639
Op Name: BLACK TEA OIL, LLC
Address: 11310 E. 21ST N. PMB #139
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4368		200 SX
SURF	8.625	265		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2018 9:30 AM
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC
Proposal Rcvd. from: CHRIS LEIKER Company: BLACK TEA OIL, LLC DBA Phone: (316) 744-5482

Proposed Plugging Method: Ordered 150 sx common cement 3% cc, 350 sx 60/40 pozmix 4% gel cement, 1900 # gel and 600 # hulls.
8 5/8" surface casing set at 265' w/200 sx cement.
5 1/2" production casing set at 4368' w/200 sx cement.
TD 4331'. Port collar set at 1777' w/400 sx cement. Anhydrite 2091' - 2111'.
Perforations: 4038' - 4048', 4146' - 4149', 4163' - 4192', 4228' - 4268' and 4282' - 4292'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2018 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2100'. Ran tubing to 3967' and pumped 150 sx common cement 3% cc w/400 # hulls. Pulled tubing to 2500'. Flushed tubing with fresh water. Waited on cement for 1 1/2 hours. Ran rod on sand-line through tubing to tag top of cement. Ran tubing to tag cement at 3120'. Pulled tubing to 3090' and pumped 1000 # gel. Pulled tubing to 2112' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1102' and pumped 120 sx cement. Cement circulated to surface. Pulled tubing to surface. Topped off production casing with 10 sx cement. Connected to 8 5/8" surface casing with immediate pressure to 500 #.

GPS: 38.80941N -100.90294W

Perfs:

Top	Bot	Thru	Comments
4282	4292		
4228	4268		
4163	4192		
4146	4149		
4038	4048		

3-16-18
KCC WICHITA
MAR 16 2018
RECEIVED

Remarks: ULTIMATE WELL SERVICE PULLING UNIT. COPELAND ACID AND CEMENT. CEMENT TICKET # 45,663.

Plugged through: TBG

INVOICED
APR 2 0 2018

District: 04

Signed Darrel Dipman
(TECHNICIAN),

CM

MAR 12 2018