

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22428-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 22-28S-13E
714 feet from S Section Line, 3355 feet from E Section Line
Lease Name: W OAKES Well #: A-1
County: ELK Total Vertical Depth: 1462 feet

Operator License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: P.O. BOX 296
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1422		150 SX
SURF	8.625	43		25 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 04/12/2018 12:00 AM
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS
Proposal Rcvd. from: JEFF MORRIS Company: _____ Phone: (620) 378-3650

Proposed Plugging Method: Set 50' 50/50 Poz blend cement plug on TD to approx. 1412'. Fill with 9# (minimum) bentonite gel to approx. 730', then set 50' cement plug to approx. 680'. Fill with gel to approx. 150', then cement to surface.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 04/12/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" tubing to 1409' gelled hole and spotted 5 sack plug. Pulled up to 688' and spotted 5 sack plug. Pulled up to 255' and circulated cement to surface. Pulled 2" and topped well off. A total of 50 sacks of pozblend cement were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DIST #3
APR 17 2018
CHANUTE, KS

DS


Remarks: WELL WAS PLUGGED DUE TO DENIED CP-111 FORM.

Plugged through: TBG

INVOICED
APR 20 2018

District: 03

Signed



(TECHNICIAN)