

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-26053-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 36-29S-13E
693 feet from S Section Line, 1962 feet from W Section Line
Lease Name: R SMITH Well #: A-1
County: WILSON Total Vertical Depth: 1501 feet

Operator-License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: P.O. BOX 296
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1300		140 SX
SURF	8.625	44		30 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS
Proposal Rcvd. from: JEFF MORRIS Company: _____ Phone: (620) 378-3650

Proposed Plugging Method: Set 50' 50/50 Poz blend cement plug on TD to approx. 1451'. Fill with 9# (minimum) bentonite gel to approx. 750', then set 50' cement plug to approx. 700'. Fill with gel to approx. 150', then cement to surface.

Plugging Proposal Received By: LARRY MARCHANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2018 9:00 AM KCC Agent: LARRY MARCHANT

Actual Plugging Report:

Ran 2 3/8" tubing to TD, pumped gel for spacer, pumped 50' plug at TD. Pulled up to 637' and pumped 50' plug, pulled up to 255' and circulated cement to surface, pulled tubing and topped well off. Used 50 sacks 60/40 Pozmix with 4% Bentonite.

Perfs:

RECEIVED
KCC DIST #3
APR 19 2018
CHANUTE, KS

LM

Remarks:

Plugged through: TBG

INVOICED

APR 20 2018

District: 03

Signed Larry Marchant
(TECHNICIAN)