

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-19141-00-00
Spot: NENWSESW Sec/Twnshp/Rge: 4-24S-18E
1125 feet from S Section Line, 3440 feet from E Section Line
Lease Name: BAKER L Well #: 1
County: ALLEN Total Vertical Depth: 983 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	868		25 SX
SURF	6.75	21		3 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2018 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RI 1" TBG INSIDE OF THE 2" PROD CSG TO 982', PMP IN CMT THRU SAME AND CIRC CMT TO SURF, POOH 1" TBG, RI EITHER 3/4" OR 1" TBG DWN THE ANNULAS, FILL SAME W/ CMT TO SURF, PO TBG, "TOP OFF" PROD CSG AND ANNULAS W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 03/12/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Operator tried for several days to run 1" pipe down well. The 2" casing was not present at surface. After several days the operator reached approximately 400' with the 1" pipe. The operator pumped and circulated cement through the 1" pipe from 400' to surface. A total of 78 sacks of portland cement was reported used to plug this well.

Top	Bot	Thru	Comments
868	983		


RECEIVED
KCC DIST # 3
MAR 30 2018
CHANUTE, KS
RD
INVOICED

Remarks:

Plugged through: TBG

District: 03

Signed

 RYAN DULUNG

(TECHNICIAN)