

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-03208-00-00  
Spot: SENEENW Sec/Twnshp/Rge: 28-23S-18E  
650 feet from N Section Line, 2890 feet from E Section Line  
Lease Name: BROOKS Well #: 1AO  
County: ALLEN Total Vertical Depth: 1222 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	925		125 SX
SURF	8	10		3 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2018 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 889', "GEL THE HOLE UP", (PMP IN A MIXTURE OF BENTONITE & WTR), FOLLOWED BY A 100' CMT PLUG ON BTM, PU TBG TO 400', PMP IN A 50' CMT PLUG, PU TBG TO 250, PMP IN AND CIRC CMT TO SURF, POOH TBG, "TOP OFF" PROD CSG W/ CMT, PRESS UP TO 250 PSI, AND SWI. RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 03/12/2018 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

**Perfs:**

Ran 2" tubing to 927'. Mixed and pumped gel. Pumped and placed a 100' cement plug at TD. Pulled tubing up to 500'. Pumped and placed a 50' cement plug at 500'. Pulled tubing up to 300'. Pumped and circulated cement from 300' to surface. Pulled tubing out of well and topped well off with cement. A total of 41 sacks of portland cement was reported used to plug this well.

Top	Bot	Thru	Comments
871	872		

RECEIVED  
KCC DIST # 3  
MAR 30 2018  
CHANUTE, KS

RD


INVOICED  
APR 20 2018

Remarks:

Plugged through: TBG

District: 03

Signed

  
ELRS  
(TECHNICIAN)