

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-03224-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 16-24S-18E
4430 feet from S Section Line, 1120 feet from E Section Line
Lease Name: CLINE Well #: C19
County: ALLEN Total Vertical Depth: 893 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.875	838		9999 SX
SURF	7	21		5 SX
SURF	7	9999		

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/12/2018 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO BTM, "GEL WELL UP", FOLLOWED BY A 200' CMT PLUG, PU TBG TO 500', PMP IN A 50' CMT PLUG, PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT-OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC.

Plugging Proposal Received By: Witness Type: NONE
Date/Time Plugging Completed: 03/13/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2" casing to 888'. Pumped and circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe. Ran 3/4" pipe down the backside off the 2" inside the 4.5" casing to 802'. Pumped and circulated cement to surface. Pulled the 3/4" pipe. Ran 1" pipe down the backside of the 4.5" casing inside the 7" surface casing to 43'. Pumped and circulated cement to surface. Pulled the 1" pipe and topped the well off with cement. A total of 162 sacks of portland cement was reported used to plug this well.

Top	Bot.	Thru	Comments
883	893		

RECEIVED
KCC DIST #3
MAR 30 2018
CHANUTE, KS

RD

INVOICED

Remarks:

APR 20 2018

Plugged through: TBG

District: 03

Signed

[Signature]

EDRS
(TECHNICIAN)