

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-03222-00-00  
Spot: SWSWNE Sec/Twnship/Rge: 16-24S-18E  
4110 feet from S Section Line, 1125 feet from E Section Line  
Lease Name: CLINE Well #: C17  
County: ALLEN Total Vertical Depth: 883 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	849		77 SX
SURF	7	20		9999 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2018 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: WILL RIH W/ 1" TBG TO 859'+/-, PMP IN AND CIRC CMT TO THE SURF; POOH TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC. NOTE: THIS WELL WAS NOT PERF'D, IS OPEN HOLE COMPLETED FROM 849' TO 883'.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 03/12/2018 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside 2" casing to 841'. Pumped and circulated cement inside 2" casing from TD to surface. Pulled 1" pipe out of 2" casing and topped casing off with cement. Ran 1" pipe on outside of the 2" casing to 231'. Pumped and circulated cement on backside of the 2" casing. Pulled pipe and topped well off with cement. A total of 71 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot.	Thru	Comments
849	883		

RECEIVED  
KCC DIST # 3  
MAR 30 2018  
CHANUTE, KS  
RD

Remarks:

Plugged through: TBG

INVOICED

APR 20 2018

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)