

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19170-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 3-25S-5E
3878 feet from S Section Line, 3044 feet from E Section Line
Lease Name: FRANK ROBISON Well #: 37
County: BUTLER Total Vertical Depth: 2563 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2390		
PROD	7	2409		50 SX
SURF	8.625	2210		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/06/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 03/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2390', DROP BAILED 2 SK CEMENT ON TOP OF PLUG. RIH WITH 1" TUBING ON BACKSIDE OF CASING @ 270'. QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 145 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE, LAYED DOWN 1" TUBING. RIH WITH TUBING @ 260', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 95 SX TO SURFACE. SDON. 3-7-2018 TAGGED CEMENT @ 250', RIH WITH TUBING @ 250', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYE DOWN TUBING, TOPPED WELL BACK TO SURFACE WITH 10 SXS.

Perfs:

Top	Bot	Thru	Comments
2409	2562	OH	

INVOICED
APR 27 2018

Remarks: COMPLAINT LIST / DENIED TA

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)