

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-23711-00-00  
Spot: NESWNWNE Sec/Twnshp/Rge: 3-25S-5E  
4331 feet from S Section Line, 2304 feet from E Section Line  
Lease Name: FRANK ROBISON Well #: 51  
County: BUTLER Total Vertical Depth: 2621 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2390		
PROD	5.5	2409		150 SX
SURF	8.625	201		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2018 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JESS EASTWOOD/JOHN HI Company: \_\_\_\_\_ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2390', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 260'-261' (4 HOLES). RIH W/TUBING @ 260', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL 2% CC 100# HULLS TO SURFACE, LAYED DOWN TUBING, SWEDGED INTO 5 1/2" CAISNG & PUMPED 75 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. TOP PLUG WITH 170 SXS TOTAL.

Perfs:

Top	Bot	Thru	Comments
2409	2621	OH	

INVOICE

Remarks: COMPLIANCE LIST / DENIED TA

APR 20 2018

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)