

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23186-00-00
Spot: SWSWNWNE Sec/Twnshp/Rge: 3-25S-5E
4098 feet from S Section Line, 2331 feet from E Section Line
Lease Name: FRANK ROBINSON Well #: 39
County: BUTLER Total Vertical Depth: 2609 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2400		
PROD	5.5	2601		125 SX
SURF	8.625	208		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2018 5:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 528-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 04/04/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TAGGED TD @ 2474'. RIH ON WIRELINE. SET CIBP @ 2400' DMP BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 260'-261' (4 HOLES). RIH W/TUBING @ 250', QWS ESTABLISHED CIRCULATION, MIXED AND PUMPED 65 SX 60/40 POZMIX 4% GEL 2% CC & 100 # HULLS TO SURFACE. LAYED DOWN TUBING. SWEDGED INTO 5 1/2" CASING. QWS MIXED & PUMPED 60 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2601	2609	OH	

INVOICED

Remarks: DENIED TA/ COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

JK